

IKO.COM/COMM

Project Profile

Office/Industrial

 **COMMERCIAL**

Project Profile

Office/Industrial

The Project

This IKO signature commercial roofing project includes the installation of a new, dependable IKO BUR Roofing System to replace a combination of single-ply, modified bit and built up roofing systems on an existing 13,935 sq. m. (150,000 sq. ft.) warehouse and corporate office facility.

The Challenge

According to installing contractor Giancarlo Bellini, President of Toitures Trois-Étoiles Inc., the main challenge came in the project's execution. "We could only work when employees were not onsite and inside the building, between 4:30 pm and 9 am," says Bellini. As a result, the project's specific timeline was adjusted to an evening-only schedule.

The Solution

Built-up Roofing (BUR) is a dependable roof system with an established track record of reliability. The most effective BUR systems are installed by skilled applicators who have invested a lot in proper equipment to apply the multiple layers of felt and asphalt on the project. BUR continues to be a prominent roof membrane choice in cities such as Montreal.

"The IKO BUR Roofing System is a proven commercial roof membrane that has passed the test of time," Bellini notes. Since the building owner was pleased with the performance of their earlier BUR roofing system, they decided to continue with that option. "IKO is one of our top roofing materials suppliers and we've been working together since 1991. It's a solid 25-year relationship," he says.

ROOFING SYSTEM DETAILS

DECK

Steel deck with gypsum thermal barrier

PRODUCTS

Two plies of 15 lb. IKO Perforated Felt • IKOTherm™ insulation
 ½" Fibreboard • Five plies of 15 lb. IKO Perforated Felt
 IKO asphalt and gravel

COMMERCIAL WARRANTY ISSUED

10-Year Limited Labour and Material Warranty

“ IKO is one of our top roofing materials suppliers and we've been working together since 1991. It's a solid 25-year relationship. ”



- Giancarlo Bellini
 President of Toitures Trois-Étoiles Inc.



PROJECT SECTOR

Commercial

ROOFING CONTRACTOR

Toitures Trois-Étoiles Inc. – Giancarlo Bellini

APPROXIMATE PROJECT SIZE

Building 1 - 5,295 sq. m. (57,000 sq. ft.)

Building 2 – 8,528 sq. m. (91,800 sq. ft.)

ROOFING SYSTEM

IKO BUR System

PROJECT START & COMPLETION DATES

October 2008 - August 2009

IKO
COMMERCIAL
ROOF
PRO



Find out more about our products now by talking to an IKO Sales Representative, your professional roofing contractor or contact us directly at: **United States 1-888-IKO-ROOF (1-888-456-7663), Canada 1-855-IKO-ROOF (1-855-456-7663)** or visit our website at: **www.iko.com**

The information contained in the brochure is for general information only and is dispensed in order to aid the design professional. In the case of a discrepancy between the recommendations made in this document and the advice of a design professional, the advice of the design professional should be followed.

The information in this document is subject to change without notice. IKO assumes no responsibility for errors that may appear in this document.