



IKO Innovi™ TPO Mechanically Attached Roofing System

Section 07 54 23 Thermoplastic Polyolefin (TPO) Membrane Roofing

This specification is not intended to substitute for specific design services provided by an architect, engineer, roof consultant, or other design professional. IKO does not perform either architecture or engineering, and it is in the building owner's interest to consult with a design professional prior to executing the specified project. The information in this document is based upon data considered to be true and accurate and is offered solely for the user's consideration, investigation and verification. The building owner will ultimately assume the entire risk as to results, quality and performance of the roofing system specified. Nothing contained herein is representative of a warranty or guarantee for which IKO Industries can be held legally responsible.

NOTE TO SPECIFIER:

In order to complete this document, items **Red in color** require your review and selection of text that is appropriate, and removal of text that is inappropriate to the project information and intended roofing system specific to your project. It is the sole responsibility of the Specifier to exercise appropriate care and sound professional judgment in the execution of this task.

This page may be deleted. Specification Section 07 54 23 begins on following page.

PART 1 – GENERAL

1.1 SUMMARY

- .1 Furnish and install a Mechanically Attached thermoplastic polyolefin (TPO) membrane roofing system from a single-source manufacturer, including:
 - .1 Roofing membrane manufacturer's requirements for the specified warranty.
 - .2 Preparation of roofing substrates.
 - .3 Wood nailers for roofing attachment.
 - .4 Vapour Barrier.
 - .5 Insulation.
 - .6 Cover boards.
 - .7 Thermoplastic Polyolefin Membrane Roofing.
 - .8 Metal roof edging and copings.
 - .9 Flashings.
 - .10 Walkway pads.
 - .11 Other roofing accessories and items necessary to install a complete weatherproof roofing system.
- .2 The roofing applicator is responsible to dispose of roofing-related demolition debris and construction waste. Manner of disposal must comply with applicable federal, state, provincial, and local regulations.
- .3 Comply with the published instructions regarding material handling, storage, and installation as provided by the roofing membrane manufacturer ("Manufacturer," hereafter), at www.IKO.com/COMM.
- .4 Commencement of work by the Contractor shall constitute their acknowledgement that this specification may be satisfactorily executed under the project conditions, and that they have met all pre-work requirements for warranty of the completed roofing system by the Manufacturer.
- .5 It is the roofing applicator's responsibility to read and comply with the entire specification for this section of the project's work. Failure to properly examine this specification and all other related project documents is not cause for any modification of the Contract Sum.

1.2 RELATED SECTIONS

- .1 Section 06 10 00 - Rough Carpentry.
- .2 Section 07 22 00 – Roof and Deck Insulation.
- .3 Section 07 62 00 - Sheet Metal Flashing and Trim.
- .4 Section 07 71 00 – Roof Specialties.
- .5 Section 07 72 00 - Roof Accessories.

- .6 Section 08 62 00 - Unit Skylights.
- .7 Section 22 10 00 - Plumbing Piping and Roof Drains.

1.3 REFERENCES

- .1 Referenced Standards: These standards form part of this specification only to the extent they are referenced as specification requirements.
 - .1 ASTM C 1177/C 1177M - Standard Specification for Glass Mat Gypsum Substrate for Use as Sheathing; 2004.
 - .2 CSA A123.21 - Standard test method for the dynamic wind uplift resistance of membrane-roofing systems; 2020.
 - .3 CAN/ULC S-704.1 Standard for Thermal Insulation, Polyurethane and Polyisocyanurate Boards, Faced; 2017.
 - .4 CAN/ULC S770 - Standard Test Method for Determination of Long-term Thermal Resistance of Closed-Cell Thermal Insulating Foams; 2015.
 - .5 ASTM C 1289 - Standard Specification for Faced Rigid Cellular Polyisocyanurate Thermal Insulation Board; 2013.
 - .6 ASTM C 1549 - Standard Test Method for Determination of Solar Reflectance Near Ambient Temperature Using a Portable Solar Reflectometer; 2009.
 - .7 ASTM D 638 - Standard Test Method for Tensile Properties of Plastics; 2010.
 - .8 ASTM D 1004 - Standard Test Method for Initial Tear Resistance of Plastic Film and Sheeting; 2009.
 - .9 ASTM D 3273 - Standard Test Method for Resistance to Growth of Mold on the Surface of Interior Coatings in an Environmental Chamber; 2000.
 - .10 ASTM D6878/D6878M - Standard Specification for Thermoplastic Polyolefin Based Sheet Roofing; 2011a.
 - .11 ASTM E 84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2013a.
 - .12 ASTM E 136 - Standard Test Method for Behavior of Materials in a Vertical Tube Furnace At 750 Degrees C; 2012.
 - .13 FM 1-28 - Design Wind Loads; Factory Mutual System; 2007.
 - .14 FM 1-29 - Roof Deck Securement and Above Deck Roof Components; Factory Mutual System; 2006.
 - .15 PS 1 - Construction and Industrial Plywood; 2009.
 - .16 PS 20 - American Softwood Lumber Standard; 2010.
 - .17 SPRI ES-1 - Wind Design Standard for Edge Systems Used with Low Slope Roofing Systems; 2007. (ANSI/SPRI ES-1).
- .2 Roofing Manuals:
 - .1 Alberta Roofing Contractors Association Standards Manual (ARCA SM).
 - .2 Roofing Contractors of BC Roofing Practices Manual (RCABC RPM).
 - .3 Canadian Roofing Contractors Association Roofing Manual (CRCA RM).
 - .4 Quebec Master Roofers Association Roofing Manual (QMRA)

- .5 Ontario Industrial Roofing Contractors Association (OIRCA)
- .6 IKO Commercial Roofing Technical Specifications Manual

1.4 SUBMITTALS

- .1 Applicator Approval Verification: Submit letter or certificate from Manufacturer verifying applicator's status as an IKO Approved Applicator (IAAP) to install the specified roofing system for the warranty type and term indicated elsewhere in the specification.
- .2 Product Data:
 - .1 Submit Manufacturer's Product Data Sheets to show that all components of roofing system, including insulation, fasteners, plates, and all accessories necessary, comply with this specification.
 - .2 If UL or FM data is required in this specification, submit documentation showing that the roofing system to be installed is UL-Classified or FM-approved, as applicable. Additionally, include UL or FM data for any individual roofing system items or components for which UL or FM data is available and applicable.
 - .3 Submit CSA A123.21 wind uplift summary report from qualified testing laboratory for roofing system.
 - .4 Submit Manufacturer's installation instructions. Wherever these instructions allow installation options, clearly indicate which option will be used by marking up the instructions.

1.5 SHOP DRAWINGS:

- .1 Submit Manufacturer's standard detail drawings as applicable to this specification and in accordance with Manufacturer's requirement for the warranty type and term indicated elsewhere in this specification.
- .2 Submit any details customized for this project for all relevant conditions.
- .3 Samples: Submit samples of each product to be used.
- .4 Warranty Application: Submit a copy of the Manufacturer's accepted and approved Warranty Application for this project.
- .5 Sample Warranty: Submit a sample of the Manufacturer's warranty of the type and term indicated elsewhere in this specification, prior to starting work.
- .6 Executed Warranty: Submit the Manufacturer's executed warranty for this project, upon substantial completion of the work.

1.6 QUALITY ASSURANCE

- .1 Applicator Qualifications: Roofing installer shall have the following:
 - .1 Current IKO Approved Applicator [Program \(IAAP\)](#) status.

- .2 Pre-Installation Conference: Before commencing work, Contractor shall schedule and attend a meeting to review the proper installation of the specified roofing system and requirements to achieve the warranty.
 - .1 Invite attendance of Architect, Roof Consultant, General Contractor, and any other parties directly influencing the quality of roofing work or affected by the performance of roofing work.
 - .2 Provide reasonable notice of the meeting schedule in advance of meeting.

1.7 DELIVERY, STORAGE AND HANDLING

- .1 Roofing products should be delivered to the job site in Manufacturer's original containers, dry, undamaged, with seals and labels intact and legible.
- .2 Store materials clear of the ground and moisture, and with weather protective covering.
- .3 Keep combustible materials well away from sources of ignition.
- .4 All materials should be stored in accordance with Manufacturer's recommendations

1.8 WARRANTY

- .1 The installed roofing system must comply with all warranty procedures required by Manufacturer, including warranty application and inspection procedures.
- .2 Warranty: Provide warranty coverage equal to the IKO [15 year] [20 year] [25 year][30 year] Diamond Shield Limited Warranty, covering membrane, roof insulation, and roofing accessories.
- .3 Scope of Coverage:
 - .1 Repair any leak in the roofing system caused by:
 - .2 Manufacturing defect.
 - .3 Defective workmanship used to install these materials.
 - .4 Ordinary wear and tear of the elements.
 - .5 Damage due to hurricanes or tornadoes.
 - .6 Hail.
 - .7 Intentional damage.
 - .8 Unintentional damage due to normal rooftop inspections, maintenance, or service.
 - .9 Products not provided by the Manufacturer, unless where written approval of the Manufacturer is provided.

Part 2 PRODUCTS

2.1 MANUFACTURER

- .1 Basis of Design: IKO Innovati TPO Roofing System, by IKO Industries, Inc., 6 Denny Road, Suite 200, Wilmington, DE 19809; IKO Industries, Ltd., 1600 42 Ave SE, Calgary, AB T2G 5B5; www.IKO.com/COMM.
- .2 Roofing systems manufactured by others may be acceptable provided the roofing system is completely equivalent in materials and warranty conditions to the Basis of Design indicated above.
- .3 Substitution Procedures: See Instructions to Bidders.

2.2 PERFORMANCE CRITERIA

- .1 Roofing System Fastening Pattern: to CSA A123.21 for wind uplift resistance as follows:
 - .1 Field: [_____].
 - .2 Perimeter Zone: [_____].
 - .3 Corner Zone: [_____].

2.3 TPO MEMBRANE

- .1 Use accepted materials meeting conditions of specified warranty/guarantee.
- .2 Membrane: Flexible, heat weldable sheet composed of thermoplastic polyolefin polymer, complying with ASTM D 6878, with polyester weft inserted reinforcement.
 - .1 Basis of Design: IKO Innovati TPO Membrane.
- .3 Membrane Thickness (nominal): [45 mil (1.14 mm)] [60 mil (1.52 mm)] [80 mil (2.03 mm)]
- .4 Exposed Face Color: [White] [Grey] [Tan]
- .5 UL Listed and FM Approved, and tested in accordance with CSA A123.21.
- .6 Puncture Resistance: 265 lbf (1174 N), minimum, when tested in accordance FTM 101C Method 2031.
- .7 Solar Reflective Index: [White: 94, minimum] [Grey: 50 minimum] [Tan: 70 minimum]
- .8 Attachment: Mechanically Attached with appropriate fasteners and plates.
- .9 Seams: Heat welded per Manufacturer's instructions.
- .10 Maximum TPO Sheet Width: [30 yr: 10' max] [25 yr: 10' max] [20 yr: 10' max] [15 yr: 12' max]

2.4 TPO ROOFING ACCESSORIES

- .1 General:
 - .1 Accessory materials supplied or recommended by Manufacturer for intended use and compatible with Manufacturer's membrane roofing system.
 - .2 Volatile Organic Compounds: Liquids shall meet VOC content limits of the authorities having jurisdiction.
- .2 Reinforced Sheet Flashing: Manufacturer's scrim reinforced membrane with same thickness and color as sheet membrane.
 - .1 Acceptable Material:
 - .1 IKO Innovi TPO Membrane.
- .3 Non-reinforced Sheet Flashing: Manufacturer's unsupported membrane flashing with same color as sheet membrane.
 - .1 Acceptable Material:
 - .1 InnoviFlash TPO Unsupported Flashing.
- .4 Insulation Adhesive: Manufacturer's two-component Low-VOC (<5 g/L) urethane adhesive formulated to adhere roofing insulation to acceptable substrates.
 - .1 Acceptable Material:
 - .1 IKO Millennium Insulation Adhesive.
- .5 Membrane Adhesive: Manufacturer's [solvent based] [Low VOC solvent based] formulated to adhere membrane and flashings to acceptable substrates.
 - .1 Acceptable Material:
 - .1 [InnoviBond TPO Membrane Adhesive LVOC;]
 - .1 [InnoviBond TPO Membrane Adhesive]
 - .1 [InnoviBond TPO Membrane Adhesive SPR (Sprayable)]
- .6 Primer: One-part penetrating primer solution to enhance the adhesion of roofing membranes and flashings.
 - .1 Acceptable Material:
 - .1 InnoviPrime TPO Primer;
 - .1 InnoviPrime TPO Primer-LVOC.
- .7 Slip Sheet: Manufacturer's 45-mil TPO Membrane.
 - .1 Acceptable Material
 - .1 IKO Innovi TPO Membrane.
- .8 Membrane Flashings: Manufacturer's standard corner, curb, sealant pocket, pipe boot, scupper, joint covers, cover strips, and various other TPO flashings appropriate to the warranty term indicated above.
 - .1 Acceptable Material
 - .1 IKO InnoviFlash TPO products.

Deleted:

- .9 Metal Termination Bars: Manufacturer's standard All-Purpose (AP) or Heavy Duty (HD) predrilled stainless-steel or aluminum bars, with appropriate anchors by manufacturer.
 - .1 Acceptable Material:
 - .1 IKO InnoviFast Termination Bars, appropriate to substrate and warranty.
- .10 Fasteners & Plates: Manufacturer's standard fasteners and plates designed for fastening Manufacturer's membrane, insulation, cover board, termination bar, batten bar to substrate.
 - .1 Acceptable Material:
 - .1 IKO InnoviFast Fasteners and Plates, as appropriate to substrate and warranty.
- .11 Miscellaneous Roofing Accessories: Provide Manufacturer's other accessories required for full installation.
 - .1 Acceptable Material:
 - .1 IKO InnoviSeal
 - .2 IKO InnoviBoot
 - .3 IKO InnoviBond
 - .4 IKO InnoviTape
- .12 TPO Coated Metal: Manufacturer's TPO coated metal to be installer-formed to terminate the roof at the perimeter of the structure, to be included in the single-source roofing system warranty.
 - .1 Acceptable Material:
 - .1 IKO InnoviEdge TPO Coated Metal.
- .13 Edge Metal Flashings: Manufacturer's preformed edge metal flashings as appropriate to edge conditions and roof drainage plan.
 - .1 Acceptable Material:
 - .1 IKO InnoviEdge Drip Edge,
 - .2 IKO InnoviEdge Gravel Stop
 - .3 IKO InnoviEdge Coping.

2.5 Walkway Pads

- .1 Flexible Walkways: Factory-formed, nonporous, heavy-duty, slip-resisting, surface-textured walkway pads sourced from membrane roofing system manufacturer.
 - .1 Acceptable Material:
 - .1 IKO InnoviStep TPO Walkway Pad.

2.6 Cover board

- .1 High-Density Polyisocyanurate: to CAN/ULC S 704.1, ASTM C 1289, Type II, Class 4, Grade 3, high-density polyisocyanurate technology bonded in-line to mineral-surfaced, fiber glass reinforced facers.

- .1 Compressive Strength: 90 psi min.
- .2 Thickness: 1/2 inch (13 mm)
- .3 R-value: 2.5 min.
- .4 Attachment: [Mechanically through-fastened] [Adhered with Insulation Adhesive]
 - .1 Acceptable Material:
 - .1 IKOTerm CoverShield.
- .1 Gypsum Board: ASTM C 1177, coated glass-mat facer, water-resistant gypsum substrate for mechanically attached roof applications.
 - .1 Thickness: [1/4 inch (6 mm)] [1/2 inch (13 mm)] [5/8 inch (16 mm)]
 - .2 Attachment: [Mechanically through-fastened] [Adhered with Insulation Adhesive]
- .1 Gypsum Board: ASTM C 1177, Heavy duty coated glass-mat facer, water-resistant gypsum substrate for fully adhered roof applications.
 - .1 Thickness: [1/4 inch (6 mm)] [1/2 inch (13 mm)] [5/8 inch (16 mm)]
 - .2 Attachment: [Mechanically fastened] [Adhered with Insulation Adhesive]

2.7 ROOF INSULATION

- .1 Preformed polyisocyanurate roof insulation boards that comply with requirements and referenced standards, in multiple layers
 - .1 Organic Reinforced Kraft Paper Organic Facer Polyisocyanurate Foam Insulation.
 - .2 Compressive Strength per CAN/ULC S 704.1 and ASTM C 1289: [20 psi] [25 psi]
 - .3 Minimum Total Insulation Package R-value: [insert R Value at or above minimum required by applicable code]
 - .4 Minimum board thickness: [insert thickness].
 - .5 Provide insulation package in multiple layers, with maximum thickness per layer: [insert thickness].
 - .6 Minimum Long-Term Thermal Resistance (LTTR): 5.7 per inch determined in accordance with CAN/ULC S770 at 75°F (24°C)
 - .7 Attachment: [Mechanically-fastened] [Adhered with Insulation Adhesive]
 - .1 Acceptable Material:
 - .1 IKOTerm Polyisocyanurate Insulation.
- .1 Coated Glass Non-organic Facer Polyisocyanurate Foam Insulation.
 - .1 Compressive Strength per CAN/ULC S 704.1 and ASTM C 1289: [20 psi] [25 psi]
 - .2 Minimum Total Insulation Package R-value: [insert R Value at or above minimum required by applicable code]

- .3 Minimum board thickness: **[insert thickness]**.
- .4 Provide insulation package in multiple layers, with maximum thickness per layer: **[insert thickness]**.
- .5 Minimum Long-Term Thermal Resistance (LTTR): 5.7 per inch determined in accordance with CAN/ULC S770 at 75°F (24°C)
- .6 Attachment: **[Mechanically fastened] [Adhered with Insulation Adhesive]**
 - .2 Acceptable Material:
 - .1 IKOTerm III Polyisocyanurate Insulation.

2.8 Tapered insulation

- .1 Tapered Insulation: Provide factory-tapered insulation boards, saddles, crickets, tapered edge strips, and other insulation shapes where indicated for sloping to drain, per slope directions on project plans.
 - .1 1. Non-organic facer: Basis of design: IKOTerm III Tapered Insulation.
 - .1 Compressive Strength: 25 psi per CAN/ULC S 704.1 and ASTM C 1289
 - .2 Attachment: **[Mechanically fastened] [Adhered with Insulation Adhesive]**
 - .1 Acceptable Material:
 - .1 IKOTerm III

2.9 WOOD NAILERS

- .1 Wood Nailers: Comply with requirements in Division 06 Section "Miscellaneous Rough Carpentry."

2.10 VAPOUR RETARDER

- .1 Self-Adhered SBS Vapor Retarder: SBS-modified asphalt sheet; suitable for application method specified.
 - .1 Acceptable Material
 - .1 IKO MVP
 - .1 IKO MVP Sand.

2.11 SUBSTRATE BOARD

- .1 Gypsum Board: ASTM C 1177, Heavy duty coated glass-mat facer, water-resistant gypsum substrate for fully adhered roof applications.
 - .1 Thickness: **[1/4 inch (6 mm)] [1/2 inch (13 mm)] [5/8 inch (16 mm)]**
 - .2 Attachment: **[Mechanically Fastened] [Adhered with Insulation Adhesive]**
- .2 Gypsum Board: ASTM C 1177, Heavy duty coated glass-mat facer, water-resistant gypsum substrate for fully adhered roof applications.
 - .1 Thickness: **[1/4 inch (6 mm)] [1/2 inch (13 mm)] [5/8 inch (16 mm)]**
 - .2 Attachment: **[Mechanically fastened] [Adhered with Insulation Adhesive]**

Part 3 INSTALLATION

3.1 GENERAL

- .1 Applicator must submit a Warranty Application to Manufacturer as notification that this project requires Manufacturer's warranty a minimum of 2 weeks prior to job commencement.
- .2 Install all components of the specified roofing system in accordance with Manufacturer's published instructions, detail drawings, and recommendations for the specified roofing system.
 - .1 Maintain copies, in either written or electronic form, of Manufacturer's applicable instructions, detail drawings, and installation recommendations at project site for duration of installation period.
 - .2 Where Manufacturer provides no instructions or recommendations, follow good roofing practices and industry standards.
- .3 Comply with applicable federal, state, and local regulations.
- .4 Perform work using competent and properly equipped personnel.
- .5 Consult Manufacturer's instructions, Product Data Sheets, product labels, and Safety Data Sheets (SDS) for specific safety instructions. Always keep all adhesives, sealants, primers and cleaning materials away from all sources of ignition.
- .6 Temporary closures and night seals, made to ensure that moisture does not infiltrate or damage any completed section of the specified roofing system, are the responsibility of the applicator. All temporary enclosure measures must subsequently be fully completed to provide a watertight condition, including completion of flashings and terminations.
- .7 Install roofing membrane only when surfaces are clean, dry, smooth and free of snow or ice. Never apply roofing membrane and/or system components during inclement weather or when ambient conditions will not allow proper application.
- .8 Consult and follow all Manufacturer recommendations for Cold Weather Installation procedures.
- .9 It is the applicator's responsibility to take all appropriate measures to protect adjacent construction, property, vehicles, and persons from damage related to their roofing work, and to repair or restore damage caused by their roofing work, including but not limited to:
 - .1 Protection from spills and overspray from bitumen, adhesives, sealants and coatings.
 - .2 Protection of metal, glass, plastic, and painted surfaces within the range of windborne overspray.
 - .3 Keep materials in their original containers as labeled by the Manufacturer until ready for use.
 - .4 Protect all completed areas of work from all traffic, including traffic by other trades.

3.2 EXAMINATION

- .1 Verify that all decks, roofing surfaces, and substrates are sufficiently flat, rigid, able to support the weights of staged materials and installers, ready to receive work, and properly slope to drains.
- .2 Ensure that site conditions are properly prepared for commencing with the roofing installation.
- .3 Verify that roof openings and penetrations are in place and set and braced and that roof drains are securely clamped in place.
- .4 Verify that wood cants, blocking, curbs, and nailers are securely anchored to roof deck at penetrations and terminations and that nailers match thicknesses of insulation.
- .5 Any unacceptable deck, site, surface, and substrate conditions should be brought to the attention of the General Contractor and Project Owner's Representative. Proceed with installation only after unsatisfactory deck or site conditions have been corrected.
- .6 Confirm that the specifications and detail drawings provided in the project documents are not in conflict with the roofing manufacturer's recommendations, instructions, and requirements for the type and term of warranty specified.

3.3 PREPARATION

- .1 Take appropriate measures to ensure that fumes from adhesive solvents are not drawn into the building through air intakes.
- .2 Prior to proceeding, prepare roof surface so that it is clean, dry, and smooth, and free of sharp edges, fins, roughened surfaces, loose or foreign materials, oil, grease and other materials that may damage the membrane.
- .3 Fill all surface voids in the immediate substrate that are greater than 1/4 inch (6 mm) wide with cut strips of IKOTherm or IKOTherm III insulation.
- .4 Seal, grout, or tape deck joints, where needed, to prevent bitumen seepage into building.

3.4 VAPOUR BARRIER INSTALLATION (SELF-ADHERED)

- .1 Remove all wrapping tape and labels from the roll before beginning. Do not remove the release film at this time. The sheet must be unrolled and aligned before installation.
- .2 Begin installation at the low point of the roof. Use chalk lines where necessary to ensure proper alignment. Note: If a drain is the lowest point, start here with the edge of the sheet bisecting the centerline of the drain.
- .3 All metal, wood, and concrete surfaces that come into contact with self-adhered vapor retarders must first be primed with Manufacturer's appropriate primer, and be permitted to dry before applying the vapour retarder.

- .4 For self-adhered vapour retarders on steel or plywood decks, prime with IKO S.A.M. Adhesive and allow them to dry as per Manufacturer's recommendations. Note: Priming is only required when the primary board layer above is not mechanically attached to the decking.
- .5 Align vapour retarder sheets over male flutes on steel decks. While aligned, remove the release film from the backside of the vapor retarder and press the vapor retarder into full contact with male flutes. Press areas in contact with the decking to ensure a full bond. The membrane shall be rolled after installation with a 75 – 100 lbs. roller to ensure adhesion.
- .6 Align successive sheets of vapour retarder with the first. All laps shall be primed with Manufacturer's appropriate primer. Always join laps over a male flute. Overlap sides by three inches (3") (75 mm) minimum. End laps shall be six inches (6") (150 mm) minimum, and stagger end laps from each other by a minimum of twenty-four inches (24") (610 mm). End laps spanning the female flutes may require support. Cut the appropriate pieces of insulation and place them within the flute so that a level continuous surface supports the end lap.
- .7 For self-adhered vapour retarders on all other suitable substrates, use a similar installation method as detailed above for steel decks.

3.5 INSULATION AND COVER BOARD INSTALLATION

- .1 Install only as much insulation as can be covered with the completed roofing system before the end of each day's work or prior to arrival of inclement weather.
- .2 Install roof insulation in courses parallel to roof edges ensuring boards are staggered as per manufacturers requirements.
- .3 Neatly and tightly fit insulation to all penetrations, projections, and nailers, with gaps not greater than 1/4 inch (6 mm). Fill gaps greater than 1/4 inch (6 mm) with acceptable insulation. Do not leave the roofing membrane unsupported over a space greater than 1/4 inch (6 mm).
- .4 **[Mechanical Fastening:]** Use appropriate fasteners and insulation plates. Engage fasteners through insulation into deck to depth and in pattern required by Manufacturer (see www.IKO.com/COMM for pattern requirements), or by Factory Mutual for the FM Class specified in PART 2, and whichever is more stringent.
- .5 **[Adhesive Attachment:]** Use appropriate insulation adhesive. Follow Manufacturer's requirements for bead spacing and/or spray pattern at www.IKO.com/COMM. Weight insulation boards during adhesive set-up period by using full buckets of adhesive or other material to ensure full contact of the adhesive to the boards.

3.6 SINGLE-PLY MEMBRANE INSTALLATION

- .1 Beginning at the low point of roof, unroll the TPO membrane over the substrate without stretching it, and allow the membrane to relax at least 30 minutes before installing. Increase the relax time in colder weather.

- .2 Always position all membrane panels and flashing materials so that they will shed water.
- .3 Install TPO membrane without wrinkles and gaps (“fishmouths”) in the seams. Perform test welds of the membrane seams and laps in accordance with the Manufacturer’s instructions and details.
- .4 Mechanically attached the TPO membrane to the substrate using appropriate fasteners and plates, and install edge securement (“base tie-ins”) as required by Manufacturer.
- .5 Install all fasteners and plates in the seams where indicated by the membrane markings, and ensure that they are fully covered by the overlapping membrane.
 - .1 Position fasteners as recommended by Manufacturer or in compliance with FM Class specified in PART 2, whichever is most stringent.
 - .2 Properly engage fasteners in the deck with head flush with the countersunk portion of the seam plate.
- .6 Edge Securement: Secure membrane with appropriate fasteners at all locations where membrane terminates or goes through an angle change greater than 1 in 12 inches (1:12”), using mechanically fastened reinforced perimeter fastening strips, plates, or metal edging as indicated or as recommended by Manufacturer.
 - .1 Exceptions: Round pipe penetrations less than 18 inches (460 mm) in diameter and square penetrations less than 4 inches (200 mm) square.
 - .2 Ensure anchorage of the TPO membrane at the roof edges using ES-1 rated edge metal or other edge metal products accepted by Manufacturer.

3.7 FLASHING AND ACCESSORIES INSTALLATION

- .1 Install flashings, including laps, splices, joints, bonding, adhesion, and attachment, in accordance with Manufacturer’s recommendations, instructions, and details.
- .2 Metal Accessories: Install edge metal, including TPO Coated Metal, drip edges, gutters, gravel stops, and copings in locations indicated on the drawings, with horizontal leg of edge member over membrane and flashing over metal onto membrane.
 - .1 Follow Manufacturer’s instructions, recommendations, and detail drawings.
 - .2 Remove any protective surface film immediately before installation.
 - .3 Install water block sealant under edge metal per Manufacturer’s instructions.
 - .4 Flash using Manufacturer’s recommended flashing product per Manufacturer’s detail drawings corresponding with the type and term of warranty specified, unless otherwise indicated.
 - .5 Install flashing material to cover the edge metal products per Manufacturer’s instructions and detail drawings. Apply addition flashing material wherever needed to meet the Manufacturer’s requirements.
 - .6 Install an additional piece of self-adhesive flashing membrane over edge metal laps to the top of the metal piece; apply appropriate TPO sealant at all intersections of flashing sections.

- .7 When the roof slope is greater than 1:12, apply appropriate TPO sealant along the back edge of the flashing.
- .3 Scuppers: Set in appropriate TPO sealant and secure to structure; flash as recommended by Manufacturer.
- .4 Roofing Expansion Joints: Install as shown on drawings and as recommended by Manufacturer.
- .5 Flashing at Walls, Curbs, and Other Vertical and Sloped Surfaces: Install Manufacturer's TPO flashing at all walls, curbs, parapets, curbs, skylights, and other vertical and sloped surfaces that the roofing membrane abuts to; extend flashing minimum 8 inches (200 mm) high above membrane surface.
 - .1 Complete the splice on the horizontal before adhering flashing to the vertical surface.
- .6 Provide termination directly to the vertical substrate as shown on Manufacturer's detail drawings.
- .7 Roof Drains:
 - .1 Taper insulation around drains to promote water flow to drainage. Use tapered insulation whenever possible to improve slope to drains (slope not to exceed Manufacturer's or designer's recommendations).
 - .2 Position membrane over substrate, then cut a hole for roof drain to allow for 0.5" to 0.75" (12 to 19 mm) of membrane to extend inside clamping ring past drain bolts.
 - .3 Make round holes in membrane to align with clamping bolts; do not cut membrane back to bolt holes.
 - .4 Apply an entire tube of water stop mastic on top of drain bowl where clamping ring seats below the membrane
 - .5 Install the roof drain clamping ring and clamping bolts; tighten all clamping bolts in order to achieve constant compression.
- .8 Flashings at Penetrations: All penetrations through the membrane must be completely flashed and sealed directly to the penetration.
 - .1 Pipes, Round or Square Supports, and similar penetrations: Flash with specified pre-molded TPO pipe flashings wherever practical; otherwise use specified self-curing flashing, if allowed for warranty type and term.
 - .2 Pipe Clusters and Unusual Shaped Penetrations: Provide penetration sealant pocket at least 2 inches (50 mm) deep, with at least 1 inch (25 mm) clearance from penetration, sloped to shed water.
 - .3 Structural Steel Tubing: If corner radii are greater than 1/4 inch (6 mm) and longest side of tube does not exceed 12 inches (305 mm), flash as for pipes; otherwise, provide a standard curb with flashing.
 - .4 Flexible and Moving Penetrations: Provide weathertight gooseneck set in sealant and secured to deck, flashed as recommended by Manufacturer.

3.8 WALKWAY PADS

- .1 Install walkway pads at all access points to the roof, around rooftop equipment that may require maintenance, and wherever indicated on the project drawings and documents.
- .2 Unroll walkway pad and allow the pad to relax prior to installation.
- .3 Install walkway pad in maximum 10' (3 m) long sections. Leave minimum 1.0" (26 mm) space between each section to allow for proper drainage. Place each section of walkway pad so that it does not result in ponding water.
- .4 Avoid applying the walkway pad over any TPO membrane seams.
- .5 Fully heat weld the perimeter of each section of walkway pad to the TPO membrane, leaving one or two 1.0" (26 mm) gaps in the weld at the low (downslope) side of the pad to allow for moisture to escape.

3.9 FIELD QUALITY CONTROL

- .1 Inspections by Manufacturer: Provide for an inspection of the roofing system for warranty purposes by an IKO Field Service Technician; Technician will issue report indicating any items which must be corrected prior to issuance of Manufacturer's warranty.
- .2 Roofing applicator will perform all corrections necessary for issuance of warranty.
- .3 3rd Party warranty/guarantee inspections: as necessary to meet conditions; inspector approved by [RCABC] [ARCA] [CRCA].

Commented [AG1]: Will we require IKO inspection for warranty?

3.10 CLEANING

- .1 Clean all contaminants generated by roofing work from building and surrounding areas, including any bitumen, adhesives, sealants, and coatings.
- .2 Repair or replace building components and finished surfaces damaged or defaced due to the work of this section; comply with recommendations of manufacturers of non-roofing components and surfaces.
- .3 Remove all leftover materials, trash, debris, equipment from project site and surrounding areas.

3.11 ONGOING CONSTRUCTION TRAFFIC AFTER ROOFING INSTALLATION

- .1 Where construction traffic must continue over finished TPO membrane, provide durable protection, and replace or repair any damaged roofing to original condition.

END OF SECTION